Standard Abbreviations and Terms

TS = Tube Steel
HSS = Hollow Structural Section
GA = Gauge
HAS = Headed Anchor Stud
DBA = Deformed Bar Anchor
LVL = Laminated Veneer Lumber
PT Slab = Post Tensioned Concrete Slab
CMU = Concrete Masonry Unit
ID = Inside Diameter
GALV = Galvanized
GYP = Gypsum or Gypcrete
LH = Left Hand
RH = Right Hand
QTY = Quantity
T&B = Top And Bottom
TOS = Top Of Steel
TOC = Top Of Concrete
TYP = Typical
STD = Standard
AFF = Above Finish Floor
ARCH = Architect/Architecturally
BOS = Bottom Of Steel
BOC = Bottom Of Concrete
CONT = Continuous
EQ= Equal
MTL = Metal
OD = Outside Diameter
PL = Plate
PAF = Powder Actuated Fastener
STRUCT = Structure/Structural
TBD = To Be Determined
UNO = Unless Noted Otherwise
WWM = Welded Wire Mesh
GLULAM = Glue Laminated
WHR = Wall Handrail
RHU = Right Hand Up
LHU = Left Hand Up

Ledger = Material (normally angle iron) fastened to building made to hold brick

Lintel = Material (normally angle iron) not fastened to building (normally bears on brick on both sides) to hold brick above opening

Shear wall and holdowns = Wall constructed to withstand lateral forces and prevent uplift. Connected to concrete slab using holdowns.

Lumber Guide

Dimensional Lumber

Standard types are doug (douglas) fir, spruce, hem fir

Actual sizes differ from nominal dimensions

Nominal dimensions less than or equal to 1” are reduced by ¼”

Nominal dimensions greater than 1” and smaller than 7” are reduced ½”

Nominal dimensions greater than 7” are reduced by ¾”

Examples:

2x4 = 1 ½”x3 ½”

6x12 = 5 ½”x11 ¼”

Engineered Lumber

Standard types are Glulam, LVL

Actual dimensions do not differ from nominal dimensions

Example:

1 ¾”x11 ¼” LVL is actually 1 ¾”x11 ¼”